



## Heating, ventilation and sanitation systems: Marking, testing, documentation and training

### Scope

SSG 3707E comprises recommendations for marking ventilation ducts, liquid and steam piping, etc. The instructions additionally comprise regulations for the training syllabus content, how settings/adjustments and testing of the plant are to be carried out and the requirements of the documentation to be produced and to be supplied along with the supplied equipment.

### Contents

<b>1</b>	<b>Marking of ventilation ducts</b> . . . . .	2
1.1	Installation . . . . .	2
<b>2</b>	<b>Marking of installation components and other</b> . . . . .	3
2.1	Installation . . . . .	3
2.2	Example of signage for marking installation components . . . . .	3
2.3	Example of marking in addition to the position number plate . . . . .	4
2.4	Other marking . . . . .	4
<b>3</b>	<b>Marking liquid and steam piping</b> . . . . .	4
3.1	Design . . . . .	4
<b>4</b>	<b>Training</b> . . . . .	5
<b>5</b>	<b>Set-up and testing</b> . . . . .	5
5.1	Set-up and testing – ventilation . . . . .	5
5.2	Set-up and testing – cooling . . . . .	7
5.3	Set-up and testing – heating . . . . .	7
5.4	Set-up and testing – water and drainage . . . . .	8
<b>6</b>	<b>Noise measurement</b> . . . . .	8
<b>7</b>	<b>Documentation</b> . . . . .	8
7.1	Object cards . . . . .	9
7.2	Operational cards . . . . .	9
7.3	Operations and maintenance instructions . . . . .	9
<b>8</b>	<b>References</b> . . . . .	11

#### Appendix 1: Object cards